



NOTES:

1. PAVING TO BE PLACED WITHIN 5 WORKING DAYS OF UTILITY REPAIR. FLOWABLE FILL TO BE BROUGHT UP TO BOTTOM OF ASPHALT WITH 7/8" COLD ROLLED STEEL PLATES TO COVER TRENCH 24 HOURS MINIMUM PRIOR TO PLACEMENT OF SURFACE MIX ASPHALT.
2. DURING COLD WEATHER, COLD MIX TO BE USED AS A TEMPORARY MEASURE. PERMANENT SM-2A PAVING TO BE PLACED WITHIN 3 WEEKS OF STARTUP OF HOT MIX PLANTS. CHECK STONE OR PLATES AT LEAST DAILY UNTIL RESURFACED.
3. SAFETY MEASURES ARE REQUIRED; FOR EXAMPLE, FLAGMEN AT ALL TIMES THE STREET IS OBSTRUCTED, BARRICADES AT NIGHT, BRACING, ETC.
4. CONTACT THE TOWN OF CHRISTIANSBURG PRIOR TO STARTING WORK.
5. EXCAVATED MATERIAL MAY BE USED AS TEMPORARY BACKFILL IN AN EMERGENCY STREET CUT, BUT IS TO BE REMOVED AND REPLACED WITH FLOWABLE FILL NOT LATER THAN THE NEXT DAY.



ENGINEERING
DEPARTMENT
100 EAST MAIN STREET
CHRISTIANSBURG, VA 24073
(540) 382-6120 PHONE
(540) 381-7238 FAX
engineering@christiansburg.org

FLOWABLE FILL
UTILITY CUT REPAIR

DATE: 11 AUG 2014
SCALE: N.T.S.
DETAIL NO.
TB-5